



UPGRADING OF KWAGGAFONTEIN LANDFILL: WORK PACKAGE 4

PROJECT: THLM/SCM18/C/WP4/2018-2019

RQF: CONSTRUCTION OF CONCRETE DRAINS

NAME OF TENDERER:

ADDRESS OF TENDERER:

.....

.....

NOTE: Please indicate the Ward in which you reside:

Ward Number:

GRADING: 2CE

CLOSING DATE: 03 SEPTEMBER 2020

CONSTRUCTION OF CONCRETE DRAINS

1. A quotation for the Masonry works for buildings at the Kwaggafontein Landfill Site
2. The scope of the works :
 - Earthworks
 - Casting of concrete
3. All bidders to be based in Thembisile Hani Local Municipality
4. A 60:40 ratio will be used for the selection of proposals, with 60% preference allocated to locals of ward 25, and 40% allocated to locals within other areas/ wards of Thembisile Hani Local Municipality.
5. Project duration: will be discussed upon appointment.
6. Quotations must be enclosed in sealed envelopes bearing the applicable Quotation heading and delivered by hand and inserted in the tender box at the Thembisile Hani Local Municipality, Kwaggafontein-C
7. Adjudication will be conducted by the principal contractor and successful bidders will be communicated with.
8. The bidders need to provide the following documentation at tender stage. If these documents were not submitted in the first round of submissions it will not be a reason to disqualify the bidder. However, the successful bidder will have to submit these documents within 7 days after acceptance of the offer.
 - CIDB Registration
 - Tax Clearance Certificate/or Tax Pin
 - VAT registration if applicable
 - Company Registration Certificate
 - Letter of Authority of Signatory
 - Competency of Key personnel and operators
 - CSD Registration Document
 - Company Profile (including previous experience)
 - Letter of Good Standing from the Department of Labour/ or Letter for Tender Purpose
9. Retention will be 10% of which 5% will be returned with the issuing of the Practical completion and the remaining 5% to be released after the Defects Liability Period.

10. Defects Liability period is 12 months from Completion.

11. Should the Contract Value exceed R1 000 000, the Sub Contractor must provide a Guarantee to the Value of 10% of the Contract Value from their preferred Financial Institution with the approval from the Principle Contractor.

12. Rates negotiable with the principal contractor upon appointment.

CONSTRUCTION OF CIVIL ENGINEERING SERVICES
KWAGGAFONTEIN LANDFILL UPGRADE
Thembisile Hani Local Municipality

SECTION 1

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
DRAINS					
site clearance					
1	Clear and strip site	m2	200		
2	Remove topsoil to nominal depth 150 mm (or other stated depth), stockpile and maintain	m2	200		
Earthworks					
EXCAVATION FOR STORMWATER CUT-OFF DRAINS					
3	a) Deeper than 0.0m but not exceeding 1.0m	m3	220		
4	b) Deeper than 1.0m but not exceeding 1.5m	m3	0		
5	Extra-over item 2.2.1 for excavation in hard rock (Provisional)	m3	25		
6	Trimming of excavations to specified dimensions and levels	m2	330		
Carting away, dumping, trimming and compaction in layers					
7	not exceeding 300mm to 95% MOD of excess material from excavations	m3	81		
Concrete					
8	a) Cast in situ concrete lining Class 25/19	m3	70		
9	b) Class F2 surface finish	m ²	330		

	Formwork				
	Formwork to cast in situ concrete lining for open drains (class finish):				
10	(b) Two sides with steel formwork on both internal and external faces (each face measured):	m ²	40		
11	(c) Ends of slabs	m ²	30		
	Steel Reinforcement				
12	High tensile Mesh, Ref.193	m ²	400		

Total construction value	
--------------------------	--

Add 15% Value Added Tax	
-------------------------	--

Total value carried to form of offer	
--------------------------------------	--

--

For Subcontractor Date:

For Contractor Date:

Tshawe Infrastructure Technologies	C.1
------------------------------------	-----